

Formularul C4

LISTA CUPRINZAND CANTITATILE DE LUCRARI

Nr.	Capitolul de lucrari		U/M	Cantitatea	Pretul unitar	Total
Crt.	Simbol					
	Denumire resursa					
	Observatii					
1	RPCJ75A1 82		MP		38,000	
	DECOPERTARE TAVANE, ZUGRAVEALA HUMA					
2	RPCR55A1 82		MP		274,000	
	CURATIREA VOPSELEI PE BAZA DE ULEI CU DECAPANT D002-12					
3	RPCJ09A1 82		MP		70,000	
	REPARATII TENCUIELI INTERIOARE DEGRADATE					
4	RPCJ36A1 82		MP		274,000	
	GLET DE IPSOS PE TENC.INT.DRIS.DE 3 MM.GROSIME EXECUTAT CU PASTA IPSOS LA PERETI SI STILPI.					
5	RPCJ36B1 82		MP		38,000	
	GLET DE IPSOS PE TENC.INT.DRIS.DE 3 MM.GROSIME EXECUTAT CU PASTA IPSOS LA TAVANE .					
6	RPCR24A1 82		MP		214,000	
	VOPSITORIE CU VOPSEA LAVABILA LA PERETI SI TAVANE					
7	RPCT19G1 82		MP		38,000	
	DEFACEREA COVORULUI PVC					
8	CG01F1 82		MP		38,000	
	SAPA SUPTOR DIN IPSOS AUTONIVELATOARE SUB PARDOSELI DE 3CM GROSIME					
9	CG03A1 82		MP		38,000	
	PARDOSELI DIN MATERIALE PLASTICE CU COVOR PVC					
10	CG05A1 82		M		40,000	
	PLINTE PVC MONTATE ORIZONT PERETI SUPRAF.>20MP					
11	RCSR31A 02		MP		98,000	
	MONTAT TAPET PVC LA PERETI , H=2.00 M					
12	CL21A 02		M		32,000	
	PROTECTIA MUCHIILOR CU COLTARE PVC					
13	IZA03A1 82		MP		20,000	
	DECAPAT VOPSEA ULEI DE PE SUPRAFETE METAL					
14	RPCR42B1 82		MP		20,000	
	VOPSIREA IN CUL.DE ULEI A TIMPL.METALICE IN 3STR.*					
15	RPCO45A1 82		BUCATA		5,000	
	RECONDITIONARE INCUIETORI USI METALICE					
	asim					
16	RPVA35A 99		MP		8,000	
	DEMONTARE CANAL DE VENTILATIE,					
17	CF24B1 82		MP		5,000	
	PLAFON SUSPENDAT RIGIPS CU STRUCTURA METALICA					
18	TRB05A25 82		TONE		10,500	
	MANIPULAREA MATERIALELOR					
19	TRA01A15 82		TONE		10,500	
	TRANSPORTUL RUTIER AL MATERIALELOR					

Total general deviz pe categoria de lucrari:

TVA 19%

TOTAL CU T.V.A. (lei)

Obiectiv: UMF CAROL DAVILA
 Obiect: SALA PROIECTOR
 Categorie: INSTALATII ELECTRICE

LISTA CUPRINZAND CANTITATILE DE LUCRARI

Nr.	Capitolul de lucrari	U/M	Cantitatea	Pretul unitar	Total
Crt.	Simbol				
	Denumire resursa				
	Observatii				
1	EA01C 99	M		126.00	
TUB DE PROTECTIE DIN MATERIAL PLASTIC, D.EXT. =16 MM					
	L: EL01 -0024:6704701 -TUB IZOLAT TIP I.P. PVC 16 MM				
2	6712447	BUCATA		60.00	
COT PVC NEPLAST.IMBIN.PRIN LIP.PN 10 DN 16 TIP G S7175					
3	6713568	BUCATA		16.00	
MUFA PVC NEPLAST.IMBIN.PRIN LIP.PN 10 DN 16 S 7176					
4	EC02A 99	M		52.00	
CABLU PT.ENERGIE EL TIP MYXF 3X1,5 MMP					
	L: EL15 -0852:4801892 -CABLU PT.ENERGIE EL. TIP MYXF 3X1,5 MMP				
5	EC02A 99	M		80.00	
CABLU PT.ENERGIE EL TIP MYXF 3X2,5 MMP					
	L: EL15 -0853:4801907 -CABLU PT.ENERGIE EL. TIP MYXF 3X2,5 MMP				
6	EA14A 99	BUCATA		3.00	
DOZA CENTRALIZATOARE 150X150 MM, MONTATA APARENT					
	L: EL03 -0001:7318975 -DOZA CENTRALIZATOARE 150X150 MM, PT				
7	ED02A 99	BUCATA		8.00	
PRIZA CU CONTACT DE PROTECTIE, PT					
	L: EL18 -0122:5536248 -PRIZA CU CONTACT DE PROTECTIE, PT				
8	ED02A 99	BUCATA		3.00	
INTRERUPATOR 10 A, PT					
	L: EL18 -0093:5502405 -INTRERUPATOR 10 A, PT				
9	ED02A 99	BUCATA		3.00	
COMUTATOR 10 A/ 250 V, PT					
	L: EL18 -0045:5500689 -COMUTATOR 10 A 250 V, PT				
10	EE12G 99	BUCATA		17.00	
CORP DE ILUM.PT.LAMPI FLUORESCENTE TUBULARE, TIP FIDA 2X18 W, COMPLET ECHIPAT					
	L: EL21B1 -0045:5103340 -CORP IL.FL.FIDA -03 220 220V 2X 20W CS				
11	EF02A 99	BUCATA		1.00	
TABLOU ELECTRIC					
	L: EL20 -0049:7348516 -TABLOU ELECTRIC				
12	EI01A 99	BUCATA		120.00	
DIBLU CU HOLSURUB M 6X40 MM					
	L: EL18A -0069:6313332 -DIBLU CU HOLSURUB M 6X40 MM				
13	EF10B1 82	BUCATA		120.00	
ASIMILAT CLEME PRINDERE					
	L: 12001 -M :631173R -CLEME PRINDERE				

Total general deviz pe categoria de lucrari:

TVA 19%

Total cu TVA (lei)

INTOCMIT

